

File No.: EW4-2787/22

Date: 22/08/23

Notice Inviting Tender / e-Tender / Quotation

Thrissur Corporation Electricity Department invites sealed quotation / open tenders / e-Tenders from eligible applicants, who fulfill the qualification criteria as stipulated in the Store Purchase Manual Kerala, Kerala PWD Code & LGSD Tender regulations for the Supply / Work mentioned in the below-tabulation sheet.

The details of the Tender are as per following :

Approximate Cost of Supply / Work	:	Rs 325120/- (Include GST)
Supply / Work Description	:	Diwanji Moola High Mast Service VLS cable laying work (East Side) as per estimate mains extension
Tender Security / EMD / Amt.	:	8200/-
Cost of Tender Form	:	700 + 84 (GST)
Tender Document on Sale	:	
A.S. approved by	:	Resolution No 41 dt 14/07/2023 by Hon'ble Council
T.S. approved by	:	Engineer TLED
Last Date & Time of issuing Tender Form	:	15/09/2023 12 pm
Last Date & Time of Submitting Tender	:	16/09/2023 12 pm
Date & Time of Opening Tender	:	16/09/2023 3 pm
Authority & Place for submit of Tender	:	Electricity Department, Thrissur Corporation - 680001

* Sale of Tender form available only after 2. P.M. everyday once tender floated.

* Applicants must have GST Registration

* Quoted rate should be inclusive of relevant Taxes

* Tender inviting officer shall have every right to revoke tender / quotation at any time without any reason

* Those who participate in work tender should own concerned electrical contract licensee.


Assistant Secretary



Thrissur Corporation Electricity Department
Estimate Mains Extension

Office reference : EW4 - 2787/22

Length

Name of Road or Locality : Diwanji Moola High Mast service, U.G. cable laying work. (East side)

Sl. No.	Name of Article	Quantity
1	Charges for Horizontal Direction Drilling method including survey of utilities, site information collection regarding underground utilities PH making, pilot drilling re-remaining pulling 100 mm dia HDPE pipe. During work @ night hours charges for uncoiling & pulling & laying LT cable through installed HDPE pipe.	98m
2	Finolex make XLPE insulated, steel armoured & overall PVC sheathed standard Aluminium conductor cable of size : 3.5C X 50 Sq.mm.	115m
3	Charges for 3.5 C x 50 Sq.mm. LT cable End jointing and mounting complete work (including 3.5 C x 50 Sq. mm. LT heat shrinkable End Joint kit & Termination.)	1 No.
4	Gband & End Termination	1 No.
	Total	
	GST (18%)	
	Net Total	

Date : 22/8/23
Overseer


Assistant Engineer

MANOJ.N.G
Assistant Engineer 1/C
Electricity Department
Thrissur Corporation